

REQUEST FOR INFORMATION (RFI) - 2

DATE: August 22, 2006
TO: All Prospective Bidders and Plan Holders
PROJECT: "30th Avenue Soccer Park"
BID NO. B06-108E
PROJECT NO. 7007

The following is in response to RFI's:

Request: *I could not find anything in the spec book regarding the metal detector. Are we to provide 1 metal detector or 6 metal detectors and what type detector.*

Response: Metal detector is not to be provided. The statement should read "Install cleanouts per CVWD std Plan S-6. Install CI caps to allow for location by a metal detector during maintenance.

Request: *Do we price it (water main) as 1" or 1-1/2".*

Response: Water plan was revised during Addendum #2. Please reference the new drawings.

Request: *If the water service is 1-1/2" as shown on the plans, will 1-1/2" Sch 40 solvent weld pipe in sizes smaller than 4" be acceptable.*

Response: Yes, SCH 40 PVC pipe is acceptable.

Request: *Will thrust blocks be required on the 1" or 1-1/2" water service piping.*

Response: Thrust blocks will not be required for the water service piping as long as it is supported fully in the trench.

Request: *Will thrust blocks be required on the gravity sewer systems for this project.*

Response: Answer: No.

Request: *How will the water and sewer lines terminate in the building pad (cap, riser, hose bib, pee trap, etc.). Will the water and sewer lines be PVC to the termination point.*

Response: Water and sewer lines will be extended to the restroom chase and capped for connection by building installer. Complete schematics will be provided from building manufacturer at a later date.

Request: *Are the compaction requirements per the specs or Greenbook? If per the specifications, are you requiring 95% compaction in a fill that is only required to be 80%.*

Response: Compaction shall be standard 85% pipe zone and 90% in non-structural areas.

Request: *Can you please clarify on who is picking up the cost for the building permit*

Response: Include in Bid

Request: *Are all the electrical, plumbing, fixtures etc. going to be included in the pre-fab building? What if anything is needed to be done by the GC according to the pre-fab building engineers? (rock base, concrete slab, sub-grade work, 95% compaction etc.)*

Response: The prefabricated restroom building includes all lights and plumbing fixtures. The General Contractor is to provide the stub out of utilities to the building (see response 6 above). The General Contractor is to provide the compacted crushed rock base for the slab installation.

Request: *Bid Schedule Item 44 Trash Enclosure and Item 67 Trash Dumpster Enclosure Are these two separate line items or are they the same*

Response: They both reference the same item.

Request: *In reference to the pre-fabricated restroom building please clarify the scope of work to be performed by the Electrical Contractor. There is a discrepancy between the amount of electrical fixtures on the building shown on CD1 and E-2. Which is correct. There are no circuits indicated on the panel schedules for the restroom building equipment*

Scope of work is for the Electrician to make connections to the prefabricated restroom building. All electrical equipment shown on the restroom drawings on sheet CD-1 will be provided by the building manufacturer. This is the correct layout. Circuits dedicated for the restroom building electrical equipment are 11A, 14B and E4 as indicated on the drawings.

Request: *Will the City supply the four 2" RPZ devices*

Response: They are provided by the CVWD.

Request: *Will CVWD be responsible for installing the four 2" RPZ devices*

Response: They are installed by the CVWD

Request: *Where will the Contractor make his point of connection*

Response: Please see the large note on the plan titled "Points Of Connection"

Request: *Is the Contractor providing the aluminum backflow enclosure. If so, what is the make and model*

Response: Contractor is to provide the backflow enclosure. It shall be a Strong Box model SBC-45AL or approved equal.

APPROVED:

William O. Bayne, P.E.
City Engineer